

**Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services
Addendum No. 1**

ADDENDUM NO. 1

CONTRACT NO. DB-823A

This Addendum No. 1 provides additional information in connection with **Contract No. DB-823A** and is hereby made a part of the Request for Proposal for the above referenced project. This Addendum No. 1 hereby modifies and takes precedence over the original Request for Proposal as though originally included therein at length. Notwithstanding the foregoing, the COMMISSION's responses contained in this Addendum No. 1 to PROPOSERS' inquiries do not modify or take precedence over the original Request for Proposal for the above referenced project.

This Addendum No. 1 is to be signed by the PROPOSER and this **Page AD1-1** is to be attached to the Technical Proposal.

This Addendum No. 1 includes pages AD1-1 through AD1-39. Addendum No. 1 is hereby accepted and agreed to by the undersigned PROPOSER.

Name of PROPOSER

Signature

Name and Title

Subscribed and sworn to
before me this _____
day of _____, 20__

My Commission expires _____, 20__

**Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services
Addendum No. 1**

A. Modifications to TAB 1: INSTRUCTIONS TO PROPOSERS

1. RFP Tab 1, Section 23.2

Add the following to Section 8: Exceptions:

“5) The PROPOSER’S Price Proposal is to reflect full compliance with the provisions as enumerated within the Request for Proposal whereas any cost savings or additions attributable to the exceptions are reserved for the pre-award negotiations.”

B. Modifications to TAB 2: TECHNICAL REQUIREMENTS

1. RFP Tab 2, Section 2.2

Replace the table of UPS units on Page 2-12 of Tab 2, Section 2.2 with the following:

	LOCATION	RACK MOUNTED QUANTITY	WINSTED CONSOLE QUANTITY	CIRCUIT RATING
1	Delaware Water Gap TB	1		208/30
2	I-78 TB	3		208/30
3	Easton-Phillipsburg TB	1		208/30
4	Trenton-Morrisville TB	4		208/30
5	Portland-Columbia TB	1		208/30
6	New Hope-Lambertville TB	3		208/30
7	Milford-Montague TB	1		208/30
8	Washington Crossing TSB	1		240/30
9	Center Bridge-Stockton TSB	1		240/30
10	Uhlertown-Frenchtown TSB	1		240/30
11	Upper Black Eddy-Milford TSB	1		240/30
12	Scudder Falls Admin/1799	3		208/30
13	Scudder Falls TB BM/AET	2		240/30
14	New Hope-Lambertville TSB	1		240/30
15	Riegelsville TSB	1		240/30
16	Rt. 611 @ I-78 TB	1		240/30
17	Northampton Street TSB	1		208/30
18	Calhoun Street TSB	1		240/30
19	Lower Trenton TSB	1		240/30
20	Riverton-Belvidere TSB	1		240/30
21	Control Center @ T-M TB		12	120/20
22	Control Center @ NH-L TB		8	120/20
23	Langhorne Maintenance	1		208/30
	Totals	31	20	

**Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services
Addendum No. 1**

2. RFP Tab 2, Section 7.8

Delete the second-to-last and last sentences of the third paragraph.

3. RFP Tab 2, Section 7.8

Replace the fourth paragraph with the following:

“The COMMISSION maintains a limited inventory of spare parts for the CONTRACTOR’S use during preventative and corrective maintenance. The COMMISSION makes no guarantee regarding the quantity or suitability of these parts. The CONTRACTOR may use the COMMISSION’S spare parts only with the COMMISSION’S prior approval. These parts are supplemental to and do not replace the CONTRACTOR’S obligation to maintain its own separate stock of spares. If the CONTRACTOR uses a COMMISSION-owned part, it must promptly replace it with a new, OEM-specified component at its own expense. The unavailability of any COMMISSION-owned spare part shall not excuse the CONTRACTOR from meeting its maintenance or performance obligations.”

4. RFP Tab 2, Section 7.8

Add the following paragraph:

“The CONTRACTOR acknowledges that on-site storage space is limited. The CONTRACTOR shall be solely responsible for the safe and secure storage, handling, and safekeeping of all spare parts, including those provided by the COMMISSION. Should on-site space prove insufficient, the CONTRACTOR shall, at its own expense, arrange for secure off-site storage that meets industry standards for protection against theft, damage, or environmental deterioration.”

C. Modifications to TAB 3: EVALUATION CRITERIA

1. No changes.

D. Modifications to TAB 4: PRICE PROPOSAL INSTRUCTIONS

1. No changes.

E. Modifications to TAB 5: AGREEMENT

1. No changes.

F. Modifications to TAB 6: GENERAL CONDITIONS

1. No changes.

G. Modifications to TAB 7: SUPPLEMENTARY CONDITIONS

1. No changes.

**Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services
Addendum No. 1**

H. Modifications to TAB 8: PROPOSAL FORMS

1. No changes.

I. Modifications to TAB 9: PREVAILING WAGE RATES

1. No changes.

J. Modifications to TAB 10: IMPLEMENTATION REQUIREMENTS

1. No changes.

K. Modifications to TAB 11: EXHIBITS

1. RFP Tab 11,

Replace Exhibit A - Hardware/Software Inventory included herein with this Addendum No. 1.

L. Responses to Inquiries Submitted as of April 29, 2026

1. **Inquiry**: Do you believe the Commission would be open to negotiating the provisions that our legal and cybersecurity teams have flagged?

Response: PROPOSERS are reminded to specify, detail and submit exceptions to any Proposal Requirements, Agreement, General Conditions, and/or Supplementary Conditions under Section 8 of their Technical Proposal. The PROPOSER'S Price Proposal is to reflect full compliance with the provisions of the Request for Proposal whereas any cost savings or additions attributable to the exceptions are reserved for the pre-award negotiations (Refer to Tab 1, Section 23.2 and additions to the same contained herein this Addendum No. 1).

2. **Inquiry**: [Company's] audited financials are kept confidential. Can we email these to DRJTBC separately ahead of the proposal due date.?

Response: To maintain the integrity of the procurement process and help ensure all submissions are securely handled, the COMMISSION requests that PROPOSERS do not email confidential financial documents separately.

Please submit your audited financials within your official proposal package by the due date. To protect your sensitive information, you may:

- a) Clearly mark the financial documentation as 'CONFIDENTIAL' or 'PROPRIETARY'.
- b) Place the financial documents in a separate, sealed envelope/file within your submission package.
- c) Include a brief letter identifying the specific sections that are proprietary and provide a justification for why this information should not be disclosed.

All properly marked confidential information will be protected to the maximum extent permitted by law, generally under the COMMISSION's Public Record Policy.

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services
Addendum No. 1

3. **Inquiry**: What physical address shall we address the proposal bond to?

Response: The Proposal Bond should be addressed to the COMMISSION's Administration Building, 1199 Woodside, Yardley, PA 19067 and is to be included as part of the Price Proposal submission.

4. **Inquiry**: Can we include proposal tabs and cover not to be counted toward the page limit? Additionally, due to page limitations, would it be ok if we did not include any questions within each of the sections and directly provide our responses?

Response: The Technical Proposal's tabs and cover are not included as part of the page limitation. These Responses to Inquiries contained herein Addendum No. 1 are made a part of the Request for Proposal and need not be reproduced as part of the PROPOSER'S Technical Proposal.

5. **Inquiry**: Can we attach additional pages on Part 1: Company References / Experience forms?

Response: Given the variety of means available for PROPOSER'S to described their experience, additional pages are not to be attached to Part 1: Company References / Experience forms.

6. **Inquiry**: How many project sheets can we submit for Part 1 Company References / Experience forms?

Response: The number of Part 1: Company References / Experience forms is to be in accordance with Tab 1, Section 23.2.

7. **Inquiry**: Assuming there are no lane closures required as part of the installation and commissioning of UPS devices. Please confirm.

1. **Response**: The Supply and Installation of UPS Units is not anticipated to require lane closures. If and when Maintenance and Protection of Traffic (MPT) is required, the CONTRACTOR will be reimbursed for costs associated with providing the same via. the Unforeseen Work Allowance.

8. **Inquiry**: Can the due date for the proposal be extended to May 28th to allow us to ensure we incorporate feedback for the responses received and ensure we submit a quality proposal?

Response: The Proposal Due Date shall remain as May 14, 2026.

9. **Inquiry**: What communication protocol is required for the UPS to integrate with Genetec for remote alarm monitoring (e.g., SNMP)?

Response: Modbus (TCP/IP) or SNMP.

10. **Inquiry**: What is the input voltage at each UPS installation location?

Response: The table of UPS units on Page 2-12 has been enhanced to include circuit rating type information (Refer to Tab 2, Section 2.2 and changes to the same contained herein this Addendum No. 1).

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services
Addendum No. 1

11. **Inquiry**: There is a discrepancy between the Equipment List and the Quantity Table in Section 2.2. Refer to the attached spreadsheet for comparison. Please confirm the correct quantities.

Response: The Existing Hardware tables of Exhibit A have been revised and, to help with understanding what changed, revisions are highlighted in yellow (Refer to Tab 11, Exhibit A - Hardware/Software Inventory and additions/modifications to the same contained herein this Addendum No. 1) whereas the quantities depicted within the table of UPS units on Page 2-12 of Tab 2, Section 2.2 remains unchanged.

12. **Inquiry**: Can the recommended spare parts be stored at one of the DRJTBC facilities?

Response: Yes, spare parts may be stored at the I-78 Toll Bridge facility where office space with access to the ESS network, desk, shelving, etc. is available (Refer to Tab 2, Section 7.8 and changes to the same contained herein this Addendum No. 1).

13. **Inquiry**: Do all active servers across all facilities have backup units (cold standby servers) available for temporary deployment during maintenance or repair of a failed unit?

Response: No. The COMMISSION has a limited number of “recycled” servers. These servers do not have the recording capacity to support all sites and are not directly identified for any one system or role on the network.

14. **Inquiry**: Are all supported systems accessible via Remote Access, or is on-prem resolution needed for some systems?

Response: Not all systems are accessible remotely; on-prem-complication support is required. Access control headend equipment, generators, UPS, A/C units, etc. require on-site support.

15. **Inquiry**: Can we be provided with a list of systems and software applications that will reach the end of support by the time of contract award?

Response: There are currently no end-of-support applications or software on the ESS network.

16. **Inquiry**: Is DRJTBC currently the registered owner of all the software licenses and maintenance agreements held with various vendors?

Response: The integrator is responsible for Service Level Agreements (SLA’s).

17. **Inquiry**: In cases of incident resolution, how many members of staff will be contacting the contractor, and is there a preferred method of communication for issues as they arise?

Response: The CONTRACTOR could be contacted by the any of the following COMMISSION representatives: Director of Control Center & ESS Operations, ESS Maintenance Manager, ESS Support Technicians, and Control Center staff. Email is the preferred method of communication for response to work orders generated by the COMMISSION’S asset management system, IBM Maximo.

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services
Addendum No. 1

18. **Inquiry**: Is there an estimated timeline for the deployment of Mobile Device Protection?

Response: No.

19. **Inquiry**: What DRJTBC phone number shall we use for shipping care of the proposal bond?

Response: The main phone number for the COMMISSION'S Administration Building (267-394-6700) can be used.

20. **Inquiry**: What is the Commission's level of expectation in regard to maintaining back-up hardware inventory? E.g. is there an expectation for the Contractor to maintain a spare Dell R550 server or Cisco 9500 series switches as redundant inventory?

Response: The CONTRACTOR should be guided by the Repair Time Requirements and Liquidated Damages Schedule (Refer to Tab 5, Section 3, Section 3.02, Paragraph A) in its determination of spares parts together with SLA's required to sustain day-to-day operation and maintenance of the ESS for the initial three (3) year maintenance period, and any maintenance period subsequently assigned (Refer to Tab 2, Section 7.8 and changes to the same contained herein this Addendum No. 1).

21. **Inquiry**: Are current servers and network appliances under warranty, and if so, do they have care packages that include advance replacement?

Response: The NVMS servers have warranties scheduled to expire in March 2027.

22. **Inquiry**: Can we use the same qualified resume for the Assistant Project Manager and Senior NVMS Technician roles?

Response: The COMMISSION does not object to the same qualified resume being used for the Assistant Project Manager and Senior NCMS Technician roles provided the CONTRACTOR has a plan for times of overlapping duties.

23. **Inquiry**: What is the term of the existing CrowdStrike Falcon Endpoint Detection and Response license subscription?

Response: The PROPOSER'S Price Proposal should assume the existing term ends on September 30, 2026.

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Milford-Montague Toll Bridge		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage		1st Floor IT Rm 125
Axis 16 channel Encoder	M7016	1st Floor IT Rm 125
PowerEdge R550 NVMS		1st Floor IT Rm 125
Belkin KVM Switch	F1DA104Z	1st Floor IT Rm 125
DVTEL 8 Channel Encoder	DVT-7608E	1st Floor IT Rm 125
Cisco Switch (Catalyst 9300 8 x 10G/25G)	N/A / 1	1st Floor IT Rm 125
Tripp Lite LCD Monitor, Keyboard, Mouse	B021	1st Floor IT Rm 125
Altronix Power Supply	R2416300UL	1st Floor IT Rm 125
Accedian Networks Demarcation Device		1st Floor IT Rm 125
APC 5KTF Step Down Transformer	N/A / 1	1st Floor IT Rm 125
APC SRT6KRMXLT 6000VA UPS	N/A / 1	1st Floor IT Rm 125
APC SRTY192RMBP Battery Pack	N/A / 8	1st Floor IT Rm 125

Milford-Montague Toll Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Genetec Synergis Cloud Link	1	IT RM Door MM125
Mercury EP 2500 Intelligent Controller	1	IT RM Door MM125
Mercury MR52 2 Door Module	7	
Mercury MR50 1 Door Module	6	
Altronix PD8 Power Distribution Board	12	
Altronix AL600ULXB Power Supply	12	
Aperio IP wireless hub	1	
Powerasonic Battery Backup	1	IT RM Door MM125

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Delaware Water Gap Toll Bridge		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage	1	Basement Door DWG003
IFS Fiber Optic Card Cage	1	Basement Door DWG003
Axis 16 Channel Encoder	1-M7016	Basement Door DWG003
Dvтел 8 Channel Encoder	DVT-7608E	Basement Door DWG003
Cisco Switch (Catalyst 9300 8 x 10G/25G)	12X48UQ	Basement Door DWG003
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000-17	Basement Door DWG003
Belkin KVM Switch	F1DA104Z	Basement Door DWG003
PowerEdge R550 NVMS	1	Basement Door DWG003
HP Server	DL380P	Basement Door DWG003
Fiber Converter	1	Basement Door DWG003
Altronix Power Supply	R2416300UL	Basement Door DWG003
APC Step Down Transformer	5KTF	Basement Door DWG003
APC 6000VA UPS	SRT6KRMXLT	Basement Door DWG003
APC Battery Pack	SRT192RMBP/8	Basement Door DWG003

Delaware Water Gap Toll Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Genetec Synergis Cloud Link	1	Basement IT RM
Mercury Intelligent Controller	1	Basement IT RM
Mercury MR52 2-Door Module	10	
Mercury MR50 1-Door Module	15	
Altronix Power Supply	25	
Altronix Power Distribution Board	25	
Comnet Power Supply	PS48VDC-5a	Basement IT RM
Comnet Managed Switch	CNGE2FE8MSPOE	Basement IT RM
Aperio IP wireless hub	1	

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Portland-Columbia Toll Bridge (Including Portland-Columbia Pedestrian Bridge)		
Rack Equipment	Model / QTY	Location in the Building
IFS R3 Fiber Optic Card Cage	1	Basement PC002
Axis 16 Channel Encoder	M7016	Basement PC002
DVTEL 8 Channel Encoder	7608E	Basement PC002
PowerEdge R550 NVMS	20DPR1	Basement PC002
Cisco Switch (Catalyst 9300 8 x 10G/25G)	12X48UQ	Basement PC002
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000	Basement PC002
Belkin Omniview Pro3 KVM Switch		Basement PC002
GSM1000X Fiber Converter		Basement PC002
Altronix Power Supply	R2416300UL	Basement PC002
APC Step Down Transformer	5KTF	Basement PC002
APC 6000VA UPS	SRT6KRMXLT	Basement PC002
APC Battery Pack	SRT192RMBP/8	Basement PC002

Portland-Columbia Toll Bridge (Including Portland-Columbia Pedestrian Bridge)		
ACS Headend Equipment	Model / QTY	Location in the Building
Genetec Synergis Cloud Link		Basement PC002
Mercury EP2500 Intelligent Controller	1	Basement PC002
Mercury MR52 2 Door Module	6	
Mercury MR50 1-Door Module	6	
Altronix PD8 Power Distribution Board	6	
Altronix AL600ULXB Power Supply	6	
Von Duprin PS914 Power Supply	1	Basement PC002
Aperio Ip Wireless Hub	1	Lobby

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Riverton-Belvidere Toll-Supported Bridge		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage		Outside Climate Controlled Rack
Cisco Cisco Switch (Catalyst 9300 8 x 10G/25G)	8X24UQ	Outside Climate Controlled Rack
Belkin KVM Switch	F1DA104Z	Outside Climate Controlled Rack
Radian Fiber Module		Outside Climate Controlled Rack
PowerEdge R550 NVMS	20DPR1	Outside Climate Controlled Rack
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000	Outside Climate Controlled Rack
APC Step Down Transformer	5KTF	Outside Climate Controlled Rack
APC 6000VA UPS	SRT6KRMXLT	Outside Climate Controlled Rack
APC Battery Pack	SRT192RMBP/8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Riverton-Belvidere Toll-Supported Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Mercury Access Control Module	EP1502	Inside Shelter Enclosure
Altronix Power Distribution	ACM4	Inside Shelter Enclosure

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Easton-Phillipsburg Toll Bridge		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage	1	3rd Floor ESS Server RM
IFS Fiber Optic Card Cage	1	3rd Floor ESS Server RM
Axis 16 Channel Encoder	1-M7016	3rd Floor ESS Server RM
Dvtel 8 Channel Encoder	DVT-7608E	3rd Floor ESS Server RM
Cisco Cisco Switch (Catalyst 9300 8 x 10G/25G)	12X48UQ	3rd Floor ESS Server RM
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000-17	3rd Floor ESS Server RM
Belkin KVM Switch	F1DA104Z	3rd Floor ESS Server RM
PowerEdge R550 NVMS	1	3rd Floor ESS Server RM
HP Server Domain Backup	DL380P	3rd Floor ESS Server RM
Fiber Converter	1	3rd Floor ESS Server RM
Altronix Power Supply	R2416300UL	3rd Floor ESS Server RM
APC Step Down Transformer	5KTF	3rd Floor ESS Server RM
APC 6000VA UPS	SRT6KRMXLT	3rd Floor ESS Server RM
APC Battery Pack	SRT192RMBP/8	3rd Floor ESS Server RM

Easton-Phillipsburg Toll Bridge		
Rack Equipment	Model / QTY	Location in the Building
Genetec Synergis Cloud Link	1	3rd Floor ESS Server RM
Mercury EP2500 Intelligent Controller	1	3rd Floor ESS Server RM
Mercury MR52 2-Door Module	9	
Mercury MR50 1-Door Module	9	
Altronix AL600ULXB Power Supply	18	
Altronix PD8 Power Distribution Boards	18	
Aperio Wireless Hub	3	2nd & 3rd Floor

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Northampton Street Toll-Supported Bridge		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage		Outside Climate Controlled Rack
PowerEdge R550 NVMS		Outside Climate Controlled Rack
Belkin KVM Switch	F1DA104Z	Outside Climate Controlled Rack
Cisco Switch (Catalyst 9300 8 x 10G/25G)	N/A / 1	Outside Climate Controlled Rack
Tripp Lite LCD Monitor, Keyboard, Mouse	B021	Outside Climate Controlled Rack
Altronix Power Supply	R2416300UL	Outside Climate Controlled Rack
Accedian Networks Demarcation Device		Outside Climate Controlled Rack
APC 5KTF Step Down Transformer	N/A / 1	Outside Climate Controlled Rack
APC SRT6KRMXLT 6000VA UPS	N/A / 1	Outside Climate Controlled Rack
APC SRTY192RMBP Battery Pack	N/A / 8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Northampton Street Toll-Supported Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Mercury Access Control Module	EP1502	Pa Shelter Enclosure
Altronix ACM4 Power Distribution		Pa Shelter Enclosure
Altronix Power Supply	AL400LXB	Pa Shelter Enclosure
Mercury Access Control Module	EP1502	NJ Shelter Enclosure
Altronix ACM4 Power Distribution		NJ Shelter Enclosure
Comnet CNGE2FE8MSPOR+Network Switch		NJ Shelter Enclosure

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

I-78 Toll Bridge @ Administration Building		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage		1st Floor IT RM
IFS R3 Fiber Optic Card Cage		1st Floor IT RM
Axis 16 Channel Encoder	M7016	1st Floor IT RM
DVTEL 8 Channel Encoder	DVT-7608E	1st Floor IT RM
Cisco Switch (Catalyst 9500)	C9500-48Y4C	1st Floor IT RM
Cisco Switch (Catalyst 9300 8 x 10G/25G)	12X48UQ	1st Floor IT RM
Belkin KVM Switch	F1DA104Z	1st Floor IT RM
PowerEdge R550 NVMS		1st Floor IT RM
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000	1st Floor IT RM
ADVA Switch		1st Floor IT RM
GSM1000X Fiber Converter		1st Floor IT RM
Altronix Power Supply	R2416300UL	1st Floor IT RM
APC Step Down Transformer	5KTF	1st Floor IT RM
APC 6000VA UPS	SRT6KRMXLT	1st Floor IT RM
APC Battery Pack	SRT192RMBP/8	1st Floor IT RM

I-78 Toll Bridge @ Administration Building		
ACS Headend Equipment	Model / QTY	Location in the Building
Aperio Wireless Hub	1	3rd Floor
Genetec Synergis Cloud Link	1	1st Floor IT RM
Altronix EP2500 Intelligent Controller	1	1st Floor IT RM
MR16 Input Board	2	
Mercury MR50 1-Door Module	21	
Altronix ACM8 Power Distribution Boards	2	
Altronix AL600ULXB Power Supply	2	
Altronix PD8 Power Distribution Boards	21	
Altronix SMP5 Power Supply	2	
Veris X100CAB Transformer	2	

I-78 Toll Bridge @ Maintenance Garage		
Rack Equipment	Model / QTY	Location in the Building
Comnet Ethernet Extender	CLFE8EOU	Garage IT RM
Cisco Switch (Catalyst 9500)	C9500-48Y4C	Garage IT RM
Cisco WS-C2960+24PC/S Network Switch		Garage IT RM
Network Interface Device		Garage IT RM
APC 6000VA UPS	SRT6KRMXLT/2	Garage IT RM
APC Battery Pack	SRT192RMBP/16	Garage IT RM
PowerEdge R550 NVMS		Garage IT RM
Altronix Camera Power Supply	R24163UC-2	Garage IT RM

I-78 Toll Bridge @ Maintenance Garage		
ACS Headend Equipment	Model / QTY	Location in the Building
Genetec Synergis Cloud Link	1	Garage IT RM
Altronix EP2500 Intelligent Controller	1	Garage IT RM
Mercury MR50 1-Door Module	18	Garage IT RM
Mercury MR16IN Input Board	1	Garage IT RM
Altronix AL600ULXB Power Supply	1	Garage IT RM
Altronix SMP5 Power Supply	1	Garage IT RM
Veris X100CAB Transformer	1	Garage IT RM

I-78 Toll Bridge @ RT-611		
Rack Equipment	Model / QTY	Location in the Building
Comnet Fiber Over Ethernet Converter	CNFE1002	Outdoor Climate Controlled Rack
Axis 16 Channel Encoder	M7016	Outdoor Climate Controlled Rack
Cisco WS-3650 POE Network Switch	8X24UQ	Outdoor Climate Controlled Rack
Belkin KVM Switch	F1DA104Z	Outdoor Climate Controlled Rack
Altronix Maximal 1RHD Power Supply		Outdoor Climate Controlled Rack
GSM1000X Fiber Converter		Outdoor Climate Controlled Rack
ADVA Switch		Outdoor Climate Controlled Rack
Canoga Perkins Fiber Converter		Outdoor Climate Controlled Rack
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000	Outdoor Climate Controlled Rack
APC SKTF Step Down Transformer		Outdoor Climate Controlled Rack
APC 6000VA UPS	SRT6KRMXLT	Outdoor Climate Controlled Rack
APC Battery Pack	SRT192RMBP/2	Outdoor Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outdoor Climate Controlled Rack

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Riegelsville Toll-Supported Bridge		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage		Outside Climate Controlled Rack
Altronix Maximal Power Supply		Outside Climate Controlled Rack
Cisco Switch (Catalyst 9300 8 x 10G/25G)	8X24UQ	Outside Climate Controlled Rack
Belkin KVM Switch	F1DA104Z	Outside Climate Controlled Rack
GSM1000X Fiber Converter		Outside Climate Controlled Rack
PowerEdge R550 NVMS		Outside Climate Controlled Rack
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000-17	Outside Climate Controlled Rack
APC Step Down Transformer	5KTF	Outside Climate Controlled Rack
APC 6000VA UPS	SRT6KRMXLT	Outside Climate Controlled Rack
APC Battery Pack	SRT192RMBP/8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Riegelsville Toll-Supported Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Mercury Access Control Module	EP1502	Pa Shelter Enclosure
Altronix ACM4 Power Distribution		Pa Shelter Enclosure
Altronix Power Supply	AL400LXB	Pa Shelter Enclosure
Mercury Access Control Module	EP1502	NJ Shelter Enclosure
Altronix ACM4 Power Distribution		NJ Shelter Enclosure

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Upper Black Eddy-Milford Toll-Supported Bridge		
Rack Equipment	Model / QTY	Location in the Building
Comnet Media Converter Cage		Outside Climate Controlled Rack
Altronix Maximal Power Supply		Outside Climate Controlled Rack
Cisco Switch (Catalyst 9300 8 x 10G/25G)	8X24UQ	Outside Climate Controlled Rack
Belkin KVM Switch	F1DA104Z	Outside Climate Controlled Rack
GSM1000X Fiber Converter		Outside Climate Controlled Rack
PowerEdge R550 NVMS	20DPR1	Outside Climate Controlled Rack
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000-17	Outside Climate Controlled Rack
APC Step Down Transformer	5KTF	Outside Climate Controlled Rack
APC 6000VA UPS	SRT6KRMXLT	Outside Climate Controlled Rack
APC Battery Pack	SRT192RMBP/8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Upper Black Eddy-Milford Toll-Supported Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Mercury Access Control Module	EP1502	Inside Shelter Enclosure
Altronix Power Distribution	ACM4	Inside Shelter Enclosure

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Uhlerstown-Frehtown Toll-Supported Bridge		
Rack Equipment	Model / QTY	Location in the Building
AMG media converter rack	AMG 210C	Outside Climate Controlled Rack
Altronix Maximal Power Supply		Outside Climate Controlled Rack
Cisco Switch (Catalyst 9300 8 x 10G/25G)	8X24UQ	Outside Climate Controlled Rack
Belkin KVM Switch	F1DA104Z	Outside Climate Controlled Rack
GSM1000X Fiber Converter		Outside Climate Controlled Rack
PowerEdge R550 NVMS		Outside Climate Controlled Rack
Tripp Lite LCD Monitor, Keyboard, Mouse	B021-000-17	Outside Climate Controlled Rack
APC Step Down Transformer	5KTF	Outside Climate Controlled Rack
APC 6000VA UPS	SRT6KRMXLT	Outside Climate Controlled Rack
APC Battery Pack	SRT192RMBP/8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Uhlerstown-Frehtown Toll-Supported Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Mercury Access Control Module	EP1502	Inside Shelter Enclosure
Altronix Power Distribution	ACM4	Inside Shelter Enclosure

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Centre Bridge-Stockton Toll-Supported Bridge		
Rack Equipment	QTY	Location in the Building
Cisco Switch (Catalyst 9300 8 x 10G/25G)	1	Outside Climate Controlled Rack
Belkin KVM	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17	1	Outside Climate Controlled Rack
PowerEdge R550 NVMS	1	Outside Climate Controlled Rack
Altronix Maximal 1RHD	1	Outside Climate Controlled Rack
LPG Stationary Tank Monitor	1	Outside Climate Controlled Rack
Axis P8221 I/O Module	1	Outside Climate Controlled Rack
Comnet C1PS Power Supply	1	Outside Climate Controlled Rack
Comnet Media Converter Cage	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17 LCD Monitor, Keyboard, Mouse	1	Outside Climate Controlled Rack
APC 5KTF Step Down Transformer	1	Outside Climate Controlled Rack
APC SRT6KRMXLT 6000VA UPS	1	Outside Climate Controlled Rack
APC SRT192RMBP Battery Pack	8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Centre Bridge-Stockton Toll-Supported Bridge		
ACS Headend Equipment	QTY	Location in the Building
Mercury EP1502 Network Controller	1	NJ Shelter
Altronix ACM4 Power Distribution	1	NJ Shelter

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

New Hope-Lambertville Toll Bridge (Including Federation Server)		
Rack Equipment	QTY	Location in the Building
Axis M7016 Encoder	2	Rack 1 - 1st Flr IT Rm
DVTel Encoder	1	Rack 1 - 1st Flr IT Rm
Cisco Switch (Catalyst 9300 8 x 10G/25G)	1	Rack 1 - 1st Flr IT Rm
Tripp Lite KVM	1	Rack 1 - 1st Flr IT Rm
Tripp Lite B021-000-17	1	Rack 1 - 1st Flr IT Rm
PowerEdge R550 NVMS	2	Rack 1 - 1st Flr IT Rm
Altronix R2416300UL Power Supply	1	Rack 1 - 1st Flr IT Rm
Bosch LTC 8786/60 BiPhase Converter	1	Rack 1 - 1st Flr IT Rm
AXIS P8221 I/O Module	1	Rack 1 - 1st Flr IT Rm
Comnet CIPS Power Supply	1	Rack 1 - 1st Flr IT Rm
HP DL360	2	Rack 1 - 1st Flr IT Rm
BCD Video Server	1	Rack 1 - 1st Flr IT Rm
Dell Server Anti Virus	1	Rack 1 - 1st Flr IT Rm
Dell Server WSUS	1	Rack 2 - 1st Flr IT Rm
HP Server SNMP	1	Rack 2 - 1st Flr IT Rm
BreifCam Analytics Server	1	Rack 2 - 1st Flr IT Rm
HP DL380 Server	4	Rack 1 & 2 (1 Each)
APC 5KTF Step Down Transformer	2	Rack 1 & 2 (1 Each)
APC SRT6KRMXLT 6000VA UPS	2	Rack 1 & 2 (1 Each)
APC SRTY192RMBP Battery Pack	16	Rack 1 & 2 (1 Each)

New Hope-Lambertville Toll Bridge (Including Federation Server)		
Rack Equipment	QTY	Location in the Building
Comcast Receiver	2	Rack 3 - 2nd Flr PCC Rm
ESS Workstation Streamvault	4	2nd Flr Video wall
ESS Workstation Streamvault	4	Rack 4 - 2nd Flr PCC Rm
KVM Switch Tripplite	2	Rack 4 - 2nd Flr PCC Rm
KVM Transmitter Tripplite HDMI Ext.	10	Rack 4 - 2nd Flr PCC Rm
DNS Server Proliant DL 360 Gen10	1	Rack 4 - 2nd Flr PCC Rm
Network Switch Catalyst 3650	2	Rack 5 - 2nd Flr PCC Rm
KVM Switch Tripplite	2	Rack 5 - 2nd Flr PCC Rm
KVM Transmitter Tripplite HDMI Ext.	10	Rack 5 - 2nd Flr PCC Rm
Backup DNS Server Proliant DL 360 Gen10	1	Rack 5 - 2nd Flr PCC Rm
APC 5KTF Transformer	3	1 Each Rack (3-5)
APC SRT5KRMXLT 5000VA UPS	1	1 Each Rack (3-5)
APC SRT192RMBP Battery Pack	8	1 Each Rack (3-5)

New Hope-Lambertville Toll Bridge (Including Federation Server)		
ACS Headend Equipment	QTY	Location in the Building
Mercury EP2500 Network Controller	1	IT Rm R147
Mercury MR16IN Input Module	2	IT Rm R147
Mercury MR16OUT Output Module	2	IT Rm R147
Life Safety Power Supply	2	IT Rm R147
Genetec Synergis Cloudlink	1	IT Rm R147
Aiphone RY-IP44 Intercom I/O Adapter	1	IT Rm R147
Mercury MR52 Door Controller	12	IT Rm R147
Mercury MR52 Door Controller	12	IT Rm R147
Life Safety Power Supply	2	IT Rm R147
Life Safety Power Distribution	4	IT Rm R147
Mercury EP2500 Network Controller	1	IT Rm R147
Mercury MR16IN Input Module	1	IT Rm R147
Mercury MR16OUT Output Module	1	IT Rm R147
Mercury MR50 Door Controller	3	IT Rm R147
Mercury EP1502 Network Controller	1	IT Rm R147
Mercury MR50 Door Controller	1	IT Rm R147
Mercury MR16IN Input Module	1	IT Rm R147
Mercury MR16OUT Output Module	1	IT Rm R147
Life Safety Power Supply	2	IT Rm R147
Aperio Wireless Hub	3	1st,2nd,3rd, floor
Life Safety Power Distribution	4	IT Rm R147

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

New Hope-Lambertville Toll-Supported Bridge		
Rack Equipment	QTY	Location in the Building
Cisco Switch (Catalyst 9300 8 x 10G/25G)	1	Outside Climate Controlled Rack
Belkin KVM	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17	1	Outside Climate Controlled Rack
PowerEdge R550 NVMS	1	Outside Climate Controlled Rack
Altronix Maximal 1RHD	1	Outside Climate Controlled Rack
Axis P8221 I/O Module	1	Outside Climate Controlled Rack
AMG media converter rack (AMG210C)	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17 LCD Monitor, Keyboard, Mouse	1	Outside Climate Controlled Rack
APC 5KTF Step Down Transformer	1	Outside Climate Controlled Rack
APC SRT6KRMXLT 6000VA UPS	1	Outside Climate Controlled Rack
APC SRT192RMBP Battery Pack	8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

New Hope-Lambertville Toll-Supported Bridge		
ACS Headend Equipment	QTY	Location in the Building
Mercury EP1502 Network Controller	1	PA Shelter
Altronix ACM4 Power Distribution	1	PA Shelter
Mercury EP1502 Network Controller	1	NJ Shelter
Altronix ACM4 Power Distribution	1	NJ Shelter

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Washington Crossing Toll-Supported Bridge		
Rack Equipment	QTY	Location in the Building
Cisco Switch (Catalyst 9300 8 x 10G/25G)	1	Outside Climate Controlled Rack
Belkin KVM	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17	1	Outside Climate Controlled Rack
PowerEdge R550 NVMS	1	Outside Climate Controlled Rack
Altronix Maximal 1RHD	1	Outside Climate Controlled Rack
LPG Stationary Tank Monitor	1	Outside Climate Controlled Rack
Axis P8221 I/O Module	1	Outside Climate Controlled Rack
Comnet C1PS Power Supply	1	Outside Climate Controlled Rack
Comnet Media Converter Cage	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17 LCD Monitor, Keyboard, Mouse	1	Outside Climate Controlled Rack
APC 5KTF Step Down Transformer	1	Outside Climate Controlled Rack
APC SRT6KRMXLT 6000VA UPS	1	Outside Climate Controlled Rack
APC SRT192RMBP Battery Pack	8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Washington Crossing Toll-Supported Bridge		
ACS Headend Equipment	QTY	Location in the Building
Mercury EP1502 Network Controller	1	NJ Shelter
Altronix ACM4 Power Distribution	1	NJ Shelter

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Scudder Falls Administration Building (Including 1799 House)		
Rack Equipment	QTY	Location in the Building
Cisco Switch (WS-C3650-8X24UQ-E)	1	1st Floor IDF Rm 105
Cisco Switch (WS-C3650-8X24UQ-E)	1	2nd Floor IDF Rm 205
Cisco Switch (WS-C3650-12X48UQ-E)	1	2nd Floor IDF Rm 205
Fortinet Firewall Fortigate 60F	1	2nd Floor Server Rm 252
BriefCam Server Prolient D380 Gen 10	1	2nd Floor Server Rm 252
Kernel-based Virtual Machine (KVM) Triplite	1	2nd Floor Server Rm 252
PowerEdge R550 NVMS	1	2nd Floor Server Rm 252
SolarWinds SNMP Server Prolient D380P	1	2nd Floor Server Rm 252
SolarWinds Orion SQL Host Server Prolient D380P	1	2nd Floor Server Rm 252
Windows Update Server (WSUS) HP Prolient DL380P	1	2nd Floor Server Rm 252
MacAfee EPO Server Orion Dell Powereage R330	1	2nd Floor Server Rm 252
Integrator Shared Drive Server Prolient DL380 Gen 10	1	2nd Floor Server Rm 252
Axis M7016 16 CH. Encoder	1	2nd Floor Server Rm 252
Active Directory Server Prolient D380P	1	2nd Floor Server Rm 252
Domain Server Prolient D380P	1	2nd Floor Server Rm 252
Backup Imaging Server Prolient D380P	1	2nd Floor Server Rm 252
APC 5KTF Step Down Transformer	1	2nd Floor Server Rm 252
APC SRT6KRMXLT 6000VA UPS	3	2nd Floor Server Rm 252
APC SRTY192RMBP Battery Pack	24	2nd Floor Server Rm 252

Scudder Falls Administration Building (Including 1799 House)		
ACS Headend Equipment	QTY	Location in the Building
Mercury EP2500 Network Controller	1	1st Floor IDF Rm 105
Mercury MR16IN Input Module	2	1st Floor IDF Rm 105
Mercury MR16OUT Output Module	2	1st Floor IDF Rm 105
Life Safety Power Supply	2	1st Floor IDF Rm 105
Genetec Synergis Cloudlink	1	1st Floor IDF Rm 105
Aiphone RY-IP44 Intercom I/O Adapter	1	1st Floor IDF Rm 105
Mercury MR52 Door Controller	12	1st Floor IDF Rm 105
Mercury MR52 Door Controller	12	2nd Floor IDF Rm 205
Life Safety Power Supply	2	2nd Floor IDF Rm 205
Life Safety Power Distribution	4	2nd Floor IDF Rm 205
Mercury EP2500 Network Controller	1	2nd Floor IDF Rm 205
Mercury MR16IN Input Module	1	2nd Floor IDF Rm 205
Mercury MR16OUT Output Module	1	2nd Floor IDF Rm 205
Mercury MR50 Door Controller	1	2nd Floor IDF Rm 205
Mercury EP1502 Network Controller	1	1st Floor 1799 house Basement
Mercury MR50 Door Controller	1	1st Floor 1799 house Basement
Mercury MR16IN Input Module	1	1st Floor 1799 house Basement
Mercury MR16OUT Output Module	1	1st Floor 1799 house Basement
Life Safety Power Supply	2	1st Floor 1799 house Basement
Aperio Wireless Hub	3	1st,2nd, floor
Life Safety Power Distribution	4	1st Floor 1799 house Basement

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Scudder Falls Toll Bridge (Including BM AET Building)		
Rack Equipment	QTY	Location in the Building
Cisco WS-C3650-12X48UQ	2	Lower Lvl L101
APC AP5719	1	Lower Lvl L101
APC KVM2132P	1	Lower Lvl L101
Genetec SV-2010EX-R18-204T-12-216	1	Lower Lvl L101
Genetec SV-2000E-R4-D200-170	1	Lower Lvl L101
Genetec SVW-501E-T5-1050-145	2	Lower Lvl L101
Dell Precision 3930	1	Lower Lvl L101
APC SRT6KRMXLT 6000VA UPS	2	Lower Lvl L101
APC SRTY192RMBP Battery Pack	16	Lower Lvl L101
Bosch PoE Midspan	4	Lower Lvl L101
StarTech HDMI & USB Extender	3	Lower Lvl L101
StarTech HDMI Extender	3	Lower Lvl L101

Scudder Falls Toll Bridge (Including BM AET Building)		
ACS Headend Equipment	QTY	Location in the Building
LifeSafety Power FP0250 Power Supply	2	Lower Lvl L101
LifeSafety Power C8 Power Distribution	2	Lower Lvl L101
LifeSafety Power D8P Power Distribution	2	Lower Lvl L101
AiPhone Barlonet 50 Intercom Relay	1	Lower Lvl L101
Genetec Synergis Cloudlink	1	Lower Lvl L101
Mercury EP2500 Access Control Panel	1	Lower Lvl L101
Mercury MR16IN Remote Input Module	11	Lower Lvl L101
Mercury MR16OUT Remote Output Module	1	Lower Lvl L101
Mercury MR52 Remote Door Unit	3	Lower Lvl L101

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Calhoun Street Toll-Supported Bridge		
Rack Equipment	QTY	Location in the Building
Cisco Switch (Catalyst 9300 8 x 10G/25G)	1	Outside Climate Controlled Rack
Belkin KVM	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17	1	Outside Climate Controlled Rack
PowerEdge R550 NVMS	1	Outside Climate Controlled Rack
Altronix Maximal 1RHD	1	Outside Climate Controlled Rack
LPG Stationary Tank Monitor	1	Outside Climate Controlled Rack
Axis P8221 I/O Module	1	Outside Climate Controlled Rack
Comnet C1PS Power Supply	1	Outside Climate Controlled Rack
Comnet Media Converter Cage	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17 LCD Monitor, Keyboard, Mouse	1	Outside Climate Controlled Rack
APC 5KTF Step Down Transformer	1	Outside Climate Controlled Rack
APC SRT6KRMXLT 6000VA UPS	1	Outside Climate Controlled Rack
APC SRT192RMBP Battery Pack	8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Calhoun Street Toll-Supported Bridge		
ACS Headend Equipment	QTY	Location in the Building
Mercury EP1502 Network Controller	1	PA Shelter
Altronix ACM4 Power Distribution	1	PA Shelter
Mercury EP1502 Network Controller	1	NJ Shelter
Altronix ACM4 Power Distribution	1	NJ Shelter

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Lower Trenton Toll-Supported Bridge		
Rack Equipment	QTY	Location in the Building
Cisco Switch (Catalyst 9300 8 x 10G/25G)	1	Outside Climate Controlled Rack
Belkin KVM	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17	1	Outside Climate Controlled Rack
PowerEdge R550 NVMS	1	Outside Climate Controlled Rack
Altronix Maximal 1RHD	1	Outside Climate Controlled Rack
LPG Stationary Tank Monitor	1	Outside Climate Controlled Rack
Axis P8221 I/O Module	1	Outside Climate Controlled Rack
Comnet C1PS Power Supply	1	Outside Climate Controlled Rack
Comnet Media Converter Cage	1	Outside Climate Controlled Rack
Tripp Lite B021-000-17 LCD Monitor, Keyboard, Mouse	1	Outside Climate Controlled Rack
APC 5KTF Step Down Transformer	1	Outside Climate Controlled Rack
APC SRT6KRMXLT 6000VA UPS	1	Outside Climate Controlled Rack
APC SRT192RMBP Battery Pack	8	Outside Climate Controlled Rack
NVENT Electronic Enclosure Air Conditioner	T431016G102	Outside Climate Controlled Rack

Lower Trenton Toll-Supported Bridge		
ACS Headend Equipment	QTY	Location in the Building
Mercury EP1502 Network Controller	1	PA Shelter
Altronix ACM4 Power Distribution	1	PA Shelter

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Trenton-Morrisville Toll Bridge		
Rack Equipment	Model / QTY	Location in the Building
IFS R3 Fiber Optic Card Cage	2	TM 1st Flr Rm 534
Axis M7016 16 CH. Encoder	1	TM 1st Flr Rm 534
DVTel DVT-7608E 8 CH.Encoder	1	TM 1st Flr Rm 534
Belkin Omniview Pro 3 KVM	1	TM 1st Flr Rm 534
Cisco (Catalyst 9300)	1	TM 1st Flr Rm 534
Cisco WS-C3650-12X48UQ POE Switch	1	TM 1st Flr Rm 534
PowerEdge R550 NVMS	2	TM 1st Flr Rm 534
Tripp Lite B021-000-17 LCD Monitor, Mouse, Keyboard	1	TM 1st Flr Rm 534
Edgewater 4000 Series Router	1	TM 1st Flr Rm 534
Comnet media converter rack	1	TM 1st Flr Rm 534
APC SRT6KRMXLT 6000VA UPS	4	TM 1st Flr Rm 534
APC SRT192RMBP Battery Pack	32	TM 1st Flr Rm 534
ESS Workstation Streamvault (video wall)	7	TM 1st Flr Rm 534
ESS Workstation Streamvault (Winsted Console)	6	1st Flr Control Center
APC Winsted Console UPS (Smart ups SMT1500C)	6	1st Flr Control Center
Orion Desk Monitors (4K 27DHDN)	48	1st Flr Control Center
Barco NV UNI2-5521 (55"24/7 monitors)	23	1st Flr Control Center
HDMI extenders	23	TM 1st Flr Rm 534
Altronics R24163000UL Power Supply	1	TM 1st Flr Rm 534

Trenton-Morrisville Toll Bridge		
ACS Headend Equipment	Model / QTY	Location in the Building
Genetec Synergis Cloudlink	1	TM 1st Flr Rm 534
Mercury EP2500 Network Controller	1	TM 1st Flr Rm 534
Mercury MR52 Door Controller	8	TM 1st Flr Rm 534
Mercury MR50 Door Controller	2	TM 1st Flr Rm 534
Mercury RIU	1	TM 1st Flr Rm 534
Comnet CNGE2FE8MSPOE Managed Switch	1	TM 1st Flr Rm 534
Comnet PS48VDC-5A Power Supply	1	TM 1st Flr Rm 534
Mercury MR52 Door Controller	1	TM 1st Flr Rm 534
Altronix PD8 Power Distribution Board	4	TM 1st Flr Rm 534
Altronix AL600ULXB Power Supply	4	TM 1st Flr Rm 534
Power Sonic battery Backup	6	TM 1st Flr Rm 534
Genetec Synergis Cloudlink	1	TM 1st Flr Rm 534
Mercury EP2500 Network Controller	1	TM 1st Flr Rm 534
Mercury MR52 Door Controller	1	TM 1st Flr Rm 534
Mercury MR52 Door Controller	9	TM 1st Flr Rm 534
Mercury MR50 Door Controller	13	TM 1st Flr Rm 534
Altronix PD8 Power Distribution Board	2	TM 1st Flr Rm 534
Aperio Wireless Hub	9	1st,2nd, floor
Altronix AL600ULXB Power Supply	2	TM 1st Flr Rm 534
Power Sonic battery Backup	3	TM 1st Flr Rm 534

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Langhorne Maintenance Building		
Rack Equipment	Model / QTY	Location in the Building
IFS R3 Fiber Optic Card Cage	2	2nd Flr Server Rm
Axis M7016 16 CH. Encoder	1	2nd Flr Server Rm
Cisco Switch (Catalyst 9300 8 x 10G/25G)	1	2nd Flr Server Rm
Cisco WS-C3650-12X48UQ POE Switch	1	2nd Flr Server Rm
PowerEdge R550 NVMS	1	2nd Flr Server Rm
Tripp Lite B021-000-17 LCD Monitor, Mouse, Keyboard	1	2nd Flr Server Rm
Edgewater 4000 Series Router	1	2nd Flr Server Rm
APC SRT6KRMXLT 6000VA UPS	1	2nd Flr Server Rm
APC SRT192RMBP Battery Pack	8	2nd Flr Server Rm
Altronics R24163000UL Power Supply	1	2nd Flr Server Rm

Langhorne Maintenance Building		
ACS Headend Equipment	Model / QTY	Location in the Building
Genetec Synergis Cloudlink	1	2nd Flr Server Rm
Mercury EP2500 Network Controller	1	2nd Flr Server Rm
Mercury MR52 Door Controller	8	2nd Flr Server Rm
Mercury MR50 Door Controller	2	2nd Flr Server Rm
Mercury RIU	1	2nd Flr Server Rm
Comnet CNGE2FE8MSPOE Managed Switch	1	2nd Flr Server Rm
Comnet PS48VDC-5A Power Supply	1	2nd Flr Server Rm
Mercury MR52 Door Controller	1	2nd Flr Server Rm
Altronix PD8 Power Distribution Board	4	2nd Flr Server Rm
Altronix AL600ULXB Power Supply	4	2nd Flr Server Rm
Power Sonic battery Backup	6	2nd Flr Server Rm
Aperio Wirless Hub	7	1st floor
Genetec Synergis Cloudlink	1	2nd Flr Server Rm
Mercury EP2500 Network Controller	1	2nd Flr Server Rm
Mercury MR52 Door Controller	1	2nd Flr Server Rm
Mercury MR52 Door Controller	9	2nd Flr Server Rm
Mercury MR50 Door Controller	13	2nd Flr Server Rm
Altronix PD8 Power Distribution Board	2	2nd Flr Server Rm
Altronix AL600ULXB Power Supply	2	2nd Flr Server Rm
Power Sonic battery Backup	3	2nd Flr Server Rm

Delaware River Joint Toll Bridge Commission
 Request for Proposals
 Contract No. DB-823A
 Network Video Management System (NVMS)
 Integrator Services

Rack Equipment	Control Center @ NJSP ROIC	QTY	Location in the Building
HP 2530-24G Switch		1	ROIC IT Rm 2nd Floor
Extron IP Link		1	ROIC IT Rm 2nd Floor
Dell Precision 7910 Server		1	ROIC IT Rm 2nd Floor
HP DL360 Server		2	ROIC IT Rm 2nd Floor
APC 5KTF Step Down Transformer		1	ROIC IT Rm 2nd Floor
APC SRT6KRMXLT 6000VA UPS		1	ROIC IT Rm 2nd Floor
APC SRT192RMBP Battery Pack		1	ROIC IT Rm 2nd Floor

Delaware River Joint Toll Bridge Commission
 Request for Proposals
 Contract No. DB-823A
 Network Video Management System (NVMS)
 Integrator Services

Lumberville-Raven Rock Pedestrian Bridge		
Rack Equipment	Model / QTY	Location in the Building
Fiber Optic Splice Enclosure	1	Outdoor Climate Controlled Rack
Fiber Optic Termination Panel, 12 Port	1	Outdoor Climate Controlled Rack
Field Hardened Ethernet Switch	1	Outdoor Climate Controlled Rack
QUINT 24VDC UPS	2	Outdoor Climate Controlled Rack
5000 BTU/H Air Conditioner	1	Outdoor Climate Controlled Rack
Lumberville-Raven Rock Pedestrian Bridge		
Camera Licenses		10
Estimated Completion Date: September 30, 2027		

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

CrowdStrike Falcon Endpoint Detection & Response (EDR) License		
Location	Server	Workstation
Milford Montague Toll Bridge	1	2
Delaware Water Gap Toll Bridge	1	5
Portland-Columbia Toll Bridge (Including Portland-Columbia Pedestrian Bridge)	1	3
Riverton-Belvidere Toll-Supported Bridge	1	1
Easton-Phillipsburg Toll Bridge	3	5
Northampton Street Toll-Supported Bridge	1	2
I-78 Toll Bridge @ Administration Building, Maintenance Garage & RT 611	2	10
Riegelsville Toll-Supported Bridge	1	2
Upper Black Eddy-Milford Toll-Supported Bridge	1	1
Uhlerstown-Frenchtown Toll-Supported Bridge	1	1
Centre Bridge-Stockton Toll-Supported Bridge	1	1
New Hope-Lambertville Toll Bridge (Including Federation Server)	4	14
New Hope-Lambertville Toll-Supported Bridge	1	2
Washington Crossing Toll-Supported Bridge	1	1
Scudder Falls Administration Building (Including 1799 House)	2	16
Scudder Falls Toll Bridge (Including BM/AET Building)	2	4
Calhoun Street Toll-Supported Bridge	1	2
Lower Trenton Toll-Supported Bridge	1	1
Trenton-Morrisville Toll Bridge	1	21
Langhorne Maintenance Building	1	3
Control Center @ NJSP ROIC	-	-
TOTALS	28	97

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

<u>Software</u>	<u>Version</u>
Genetec	5.13.1.0 (121.36)
Microsoft Windows workstation and Server	Windows 11 Pro / Windows Server 2022 Standard
RGB Spectrum	
AiPhone IX	
Fortigate VPN	

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part #	Description: Milford-Montague Toll Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	24
GSC-5.13	Security Center Version 5.13.	1

Part Number	Description: Delaware Water Gap Toll Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	38
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Portland-Columbia Toll Bridge (Including Portland-Columbia Pedestrian Bridge)	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	31
GSC-5.13	Security Center Version 5.13.	1

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part #	Description: Riverton-Belvidere Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	12
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Easton-Phillipsburg Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	54
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Northampton Street Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	14
GSC-5.13	Security Center Version 5.13.	1

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part #	Description: I-78 Toll Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	94
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Riegelsville Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	12
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Upper Black Eddy-Milford Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	12
GSC-5.13	Security Center Version 5.13.	1

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part #	Description: Uhlerstown-Frenchtown Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	22
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Centre Bridge-Stockton Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	15
GSC-5.13	Security Center Version 5.13.	1

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part Number	Description: New Hope-Lambertville Toll Bridge	Quantity
GSC-Base-E	Genetec Security Center (GSC) Base Enterprise Package. Includes Synergis Enterprise Package with Access Manage support, Remote Security Desk, Badge Designer. Includes Omnicast Enterprise package with Archiving and Auxiliary Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Failover Cameras, Hardware Matrix Support, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Failover Directory Role, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile).	Supported
SVW-300-T3-1060-I7	Streamvault workstation SV-300. TOWER CORE I7-6700, 8GB RAM, 275GB SSD, 1TB, GTX1060, Single PS, WIN 10 PRO.	1
SY-MR52-S3	Mercury MR52 2-reader interface module Series 3 (8 inputs, 6 relays, PCB only, software connections included)	79
Sy-MR50-S3	Mercury MR50 1-reader interface module Series 3 (2 inputs, 2 relays, PCB only, software connections included)	7
SY-MR16IN-S3	Mercury MR16IN 16-input Monitor Module Series 3 (2 relays, PCB only, software connections included)	2
SY-MR16OUT-S3	Mercury MR16OUT 16-relay Output Control Module Series 3 (PCB only, software connections included)	4
SY-LP1502	Mercury Intelligent Controller, Linux Based, 8In/4Out/2Rd (Software Connections included)	6
GSC-1SDK-RealN-FR	One (1) Genetec SDK connection for RealNetworks with SAFR Facial Recognition.	1
GSC-1AD-USCH	Security Center Active Directory Integration (users and cardholders) Enables Windows user accounts will be linked to Security Center user and Synergis cardholder accounts. Only available with Synergis Professional or Enterprise packages.	1
GSC-Login-Site	Site License for Genetec Security Desk client connections (incl. Web Client & Mobile) (Only available with Synergis and/or Omnicast Enterprise packages and/or AutoVu Standard package).	Supported
GSC-1SCFED	1 Federated Security Center 4.0 (or higher) Directory connection. Must purchase Omnicast or Synergis Enterprise Package or AutoVu Standard.	23
GSC-1SCFED-20	1 Federated Security Center 4.0 (or higher) Directory connection - 20 entities or less (cameras, readers or Sharp). Must purchase Omnicast or Synergis Enterprise Package or AutoVu Standard.	1
GSC-1MobileU	One (1) Genetec Security Mobile app connection Supported only with GSC Mobile	25
Sy-MR50	Mercury MR50 1-reader interface module (2 inputs, 2 relays, PCB only)	103
Sy-MR52	Mercury MR52 2-reader interface module (8 inputs, 6 relays, PCB only)	58
Sy-MR16IN	Mercury MR16IN 16-input Monitor Module (2 relays, PCB only)	11
GSC-1SDK-BRIEFCAM-VSEnterprisC		5
GSC-1SDK-BRIEFCAM-VSEnterprisS		4
GSC-1SDK-ACTIVU-VideoWall		2
Sy-EP1502	Intelligent Controller, 16MB RAM Ethernet 2In/2Out/2Rd	3
GSC-1SDK-VuWall-VuWall2	One (1) Genetec SDK connection for VuWall with VuWall2.	14
Sy-IN100	one reader	7
GSC-Sy-E-1R	One (1) reader connection (not required if hardware purchased with software)	135
GSC-Sy-E-1WR	Created based on GSC-Sy-E-1R	7
GSC-Sy-E-1GCHM	One (1) Global Cardholder Management connection to a central system (max. 1 per system). Central system must be a Synergis Enterprise system.	1
GSC-Om-E-1C	1 camera connection	39
GSC-5.13	Security Center Version 5.13.	1

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part #	Description: New Hope-Lambertville Toll-Supported	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	22
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Washington Crossing Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	12
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Scudder Falls Administration Building (Including 1799 House)	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	55
GSC-5.13	Security Center Version 5.13.	1

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part #	Description: Scudder Falls Toll Bridge (Including BM AET)	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
SY-MR16IN-S3	Mercury MR16IN 16-input Monitor Module Series 3 (2 relays, PCB only, software connections included)	2
SY-MR16OUT-S3	Mercury MR16OUT 16-relay Output Control Module Series 3 (PCB only, software connections included)	1
SV-2010EX-R18-204T-12-216	Streamvault 2010EX series. 2U 18 BAY, (2) Xeon Silver 4116, 16GB RAM, OS RAID1 (2) 240GB SSD, 204TB RAW (17) 12TB, RAID5, (4)x1GbE Ports, (2)x10GbE SFP+ Ports, WIN SRV 2016. Dual PS. Genetec Security Center pre-installed. License sold separately.	Supported
SV-2000E-R4-D200-170	Streamvault 2000E Appliance - 2U 4 BAY, Xeon E3-1270V6, 16GB RAM, (2) 200GB SSD, Windows 2016, Dual PS, Genetec Security Center pre-installed. License sold separately.	1
SVW-501E-T5-1050-145	Streamvault Workstation SVW-501E - Tower, Xeon W-2145, (1) 2.5" SFF Bay + (4) 3.5" LFF Bays, 16GB RAM, 1TB HDD, Windows 10 Pro, 256GB SSD, (2) 1GbE, NVIDIA GTX1050TI, Single PS, Genetec Security Center pre-installed. License sold separately.	Supported
GSC-1Login	1 Genetec Security Desk, Web Client or Mobile connection	4
GSC-Om-P-1C	1 camera connection	82
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Calhoun Street Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	15
GSC-5.13	Security Center Version 5.13.	1

Delaware River Joint Toll Bridge Commission
Request for Proposals
Contract No. DB-823A
Network Video Management System (NVMS)
Integrator Services

Part #	Description: Lower Trenton Toll-Supported Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	19
GSC-5.13	Security Center Version 5.13.	1

Part #	Description: Trenton-Morrisville Toll Bridge	Quantity
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-Om-P-1C	1 camera connection	68
GSC-5.13	Security Center Version 5.13.	1

Part Number	Description: Langhorne Maintenance Building	Qty
GSC-Base-P	Genetec Security Center (GSC) Base Professional Package. Includes Synergis Professional Package with 2 Access Managers, Remote Security Desk, and Badge Designer. Includes Omnicast Professional Package with Archiving support, Media Router, Audio, Remote Security Desk, Camera Sequences, Camera Blocking, Camera Dewarping, Time Zone, Edge recording, trickling and archive transfer, Keyboard and Joystick Support. Includes AutoVu Standard Package. Other features included: Threat Level module, Plan Manager Advanced for GIS Map servers with unlimited entities, Active Directory Integration, an authentication role, an Active Directory Federation services connection, Intrusion Manager Base, Sipelia Base, Import Tool, Max Occupancy, Mustering Task, Visitor Management Module, Sipelia Public Address, SIP Trunking. KiwiVision Video Analytics including 300 channels for Privacy Protector, Security Analytics and People Counter. Includes 5 client connections (Security Desk, Web or Mobile). Limited to: 256 readers, 2 Access Managers, 10 clients, 250 cameras, 10 clients, and 20 Archivers.	Supported
GSC-1SCFED	1 Federated Security Center 4.0 (or higher) Directory connection. Must purchase Omnicast or Synergis Enterprise Package or AutoVu Standard.	1
GSC-Om-P-1C	1 camera connection	42
GSC-5.13	Security Center Version 5.13.	1